




प.सं.: २०८०/०८१

च.नं.:

# कोहलपुर नगरपालिका नगर कार्यपालिकाको कार्यालय

कोहलपुर, बाँके  
लुम्बिनी प्रदेश, नेपाल  
योजना तथा अनुगमन उपशाखा



Google Plus Code

6M2Q+5V7 Kohalpur

मिति: २०८०/१२/२१


## बिषय: दरभाउपत्र पेश गर्ने सम्बन्धमा

श्री नगरपालिकामा सूचिदर्ता भएका/नभएका सबै फर्महरु।

उपर्युक्त सम्बन्धमा यस कोहलपुर नगरपालिका वडा नं. १० मा आ.ब २०८०/०८१ को बार्षिक स्विकृत कार्यक्रम अन्तर्गत वडा समितिको मिति २०८०/१०/२३ को निर्णय अनुसार बजेट पुस्तिका शिर्षक नं. ३४७ बाट रु.२,५०,०००। ( दुइ लाख पचास हजार मात्र ) बजेट व्यवस्थापन भएकोले आभारभुत स्वास्थ्य केन्द्रमा फलामको सिढी तथा ट्रष्ट निर्माण कार्यका लागी संलग्न BOQ भरी तपशिल बमोजिमका कागजात सहित ७ (सात) दिन भित्र यस कार्यालयमा पेश गर्नुहुन जानकारीका लागी सबैमा यो सूचना प्रकाशित गरिएको छ ।

### तपशिल

- १.दररेट पेश गरेको निवेदन
- २.आ.ब. २०८०/०८१ को लागि फर्म र इजाजत पत्र नविकरण भएको प्रमाणपत्रको प्रतिलिपी।
- ३.मु.अ.करमा दर्ता भएको प्रमाणपत्रको प्रतिलिपी।
- ४.आ.ब. ०७९/८० को कर चुक्ता प्रमाणपत्रको प्रतिलिपी ।



धोलकराज ढकाल  
प्रमुख प्रशासकीय अधिकृत



info@kohalpurmun.gov.np, plan.section@kohalpurmun.gov.np



www.kohalpurmun.gov.np



www.facebook.com/kohalpurmun



+९७७-०८१-५४०००९



www.twitter.com/kohalpurmun





**Kohalpur Municipality**  
**Office of the Municipal Executive**  
**Kohalpur, Banke**  
**Lumbini Province, Nepal**

**Bill of Quantity (BOQ)**

A. The Rate quoted here under shall be inclusive of:


1. Supplying the materials along with accessories to the site.
2. Fixing and erecting them in position as per general practices, specifications and instructions of Site In-charge.
3. Tests and Maintenance up to the period, specified in the agreement.

B. The itemwise rate should be quoted without VAT.

**Name of the Project :- Adharbhat swasthye kendra falamko sidi tatha truss nirman.**

**Type of work :- Truss works.**

**Site Location of Project Implementation :- Kohalpur Mun. ward no.-10, Adharbhat swasthye kendra, Banke**



धोलकराज ठकाल  
प्रमुख प्रशासकीय अधिकृत  
FY: 2080/081

S.No.	Description of Work	Unit	Qty.	Rate (NRs.) Excluding VAT		Total Amount (NRs.)	Remarks
				In Figure	In Words		
<b>A</b>	<b>Civil/Construction work :-</b>						
1.00	Supplying and installation of hording board specifying brief of project as per specified size, shape and instruction of site incharge all complete.	Job.	1.00				
2.00	Site clearance with surface dressing & surface levelling including excavation in foundation in soft soil .	Sq.m.	43.56				
3.00	Providing & laying boulder soling in foundation, floor etc. laid in line and level filling the gap with sand, ramming, watering etc. all complete as per drawing, technical specification and instruction of the site engineer	Cu.m.	4.36				
4.00	Providing, laying , vibrating and curing plain cement concrete M10 (1:3:6) in floor, foundation with cement, sand and Crushed stone aggregate finishing to approved level, lines and dimensions all complete as per drawings, specifications and instruction of the site engineer.	Cu.m.	3.29				
5.00	M.S. Truss Work with one coat Primer	Kg.	313.80				
6.00	Providing, fitting, fixing of 0.41mm (26 guage Colour) CGI sheet roofing work including all required materials,labour equipment etc. all complete work as per standard specification and instruction of site engineer.	Sq.m.	46.58				
7.00	Supply, cutting, welding, fabricating as per requirement & erection of various dimensions of Channel Profile, various dia. medium class MS pipe for MS staircase.	Kg.	285.00				
8.00	Prepared enamel paint application two coat after cleaning surface by lincd oil (primer)	Sq.m.	5.10				
9.00	Procurement and supply of LLDPE Plastic tank-NS Certefied-1000 Litres	No.	1.00				
Total Amount NRs.							
VAT (13%) :							
Grand Total Amount with VAT :							
Grand Total in words :							

Name of Contractor :

Authorized Signature :

Seal :

Date :