

## कोहलपुर नगरपालिका

नगर कार्यपालिकाको कार्यालय

प.सं.:- ०७८/०७९ च.नं. :-<sub>2</sub>9036

कोहलपुर, बाँके

फोन नं.०८१-५४०००९

मितिः २०७९/०१/१३

श्री नगरपालिकामा सुचिदर्ता भएका सबै फर्महरू ।

विषयः दरभाउ पत्र पेश गर्ने सम्बन्धमा।

प्रस्तुत विषयमा यस कोहलपुर नगरपालिकाको कार्यालयमा बारुणयन्त्र चालक एंवम आपतकालीन संचालन केन्द्रको भवन निर्माण गर्नुपर्ने भएको हुदा उक्त कार्य गर्नको लागि संलग्न दरभाउपत्रमा तपाईको कबोल दर रेट भरी तपशिल बमोजिमका कागजात सहित आजका मिति देखि ७ (सात) दिन भित्र यस कार्यालयमा पेश गर्नु हुन अनुरोध गरिन्छ। कोटेशन नगरपालिकाको इमेल kohalpurmungmail.com मा समेत पठाउन सिकने छ। तपशिलः

- १. आ.ब. २०७८/०७९ को लागि फर्म निवकरण भएको प्रमाणपत्रको प्रतिलिपी।
- २. मु.अ.करमा दर्ता भएको प्रमाणपत्रको प्रतिलिपी।
- ३. आ.ब. ०७७/७८ को कर चुक्ता प्रमाणपत्रको प्रतिलिपी ।

## Kohalpur Municipality Office of Kohalpur Municipal Executive Kohalpur,Banke

## BILL OF QUANTITY

Name of project :-Driver & Qrt Room.

Location :- Kohalpur Municipality, Office, Banke.



Sno.	Description of work	Unit	Quantity	Rate in figure	Rate in words	Total Amount	Remarks
1.0	Earth work Excavation for Foundation	cum.	7.02				
2.0	Stone Soling in Foundation	cum.	4.43				
3.0	Pcc (1:2:4) in natural River Aggregate	cum.	3.92				
4.0	Brick work (1:4) Cement sand motar	cum.	10.59				
5.0	Supply laying cutting and fixing Black iron pipe (1.5") all complected work	kg.	289.44				
6.0	CGI Sheet roof with colour26#	sqm	16.70				
7.0	(Almunium swing Door and hings door with almunium composite pannel) supply and fixing of almunium door with out ventilation section size,65*38*1.2 all complect work	sqft	54.00				
	Supply Fixing Fitting Inpostiong GI under framed using steel branded chanel and fixing 12mm thick Gypsum board (complected desiging work)	sqft	160.00 90.40				
9.0	Plastering work (1:4) cement sand	sqm.					
10.0	Electrification work	Job	1.00				
11.0	Painting work	sqm.	90.40		Total Rs.		
					VAT @ 13% Rs.		
					Grand Total with VAT Rs.		

Name of Contractor:-Contractor Stemp:-