




कोहलपुर नगरपालिका
नगर कार्यपालिकाको कार्यालय

प.सं.:- ०७९/०८०

च.नं. :- ९४२



मिति २०७९/०७/२९


श्री यस कोहलपुर नगरपालिकामा सुचिदर्ता भएका सबै फर्महरु।

विषय: दरभाउ पत्र पेश गर्नेसम्बन्धमा।

प्रस्तुत विषयमा यस कोहलपुर नगरपालिका वडा नं ०८ स्थित डम्बरको घरदेखि प्रेम वलीको घरसम्म सडक कालोपत्रे कार्य कोटेशन मार्फत गर्नुपर्ने भएकाले संलग्न दरभाउपत्रमा तपाईंको कबोल दर रेट भरी तपशिल बमोजिमका कागजात सहित आजका मिति देखि ७ (सात) दिन भित्र यस कार्यालयमा पेश गर्नु हुन अनुरोध गरिन्छ।

तपशिल:

१. आ.ब. २०७९/०८० को लागि फर्म नविकरण भएको प्रमाणपत्रको प्रतिलिपी।
२. मु.अ.करमा दर्ता भएको प्रमाणपत्रको प्रतिलिपी।
३. आ.ब. ०७८/७९ को कर चुक्ता प्रमाणपत्रको प्रतिलिपी।
४. नागरिकताको प्रमाणपत्र प्रतिलिपी।


टिकाश कार्की
प्रमुख प्रशासकीय अधिकृत



Kohalpur Municipality
Office of the Municipal Executive
Kohalpur, Banke
Lumbini Province, Nepal



Bill Of Quantities

Office/Project :- KOHALPUR MUNICIPALITY/Ward 8

Name of the Project :- Dammar ko ghar dekhi prem oli ko ghar samma sadak kalopatre

Type of work :- Construction of Black Top road

Site Location of Project :- Kohalpur Mun. ward no.-8,

Estimated Amount with Vat:-

FY : 2079/080

S.No.	Description of Works	Unit	Quantity	Rate (NRs)		Amount (NRs.)	Remarks
				In Figure	In Word		
A.	GENERAL ITEMS						
1	Provide and installation of project information board of size 1.80 m x 1.20 m along with iron posts including excavation, concreting, backfilling etc all complete as per DoR Standard specification for Road and Bridge Works.	Job	1.00				
				Sub - Total (A)			
B	Pavement Works						
1	Scarifying the existing road surface to a depth of 50 mm and disposal of scarified Material with in all lifts and lead as per Drawing and Technical	Cu.m	540.00				
2	Providing, laying, spreading, watering, levelling and compaction of natural sand gravel subbase grading as per table 12.1 of standard specification	Cu.m	48.00				
3	Providing, laying, spreading, watering, levelling and compaction of crusher run materials for base course lead upto 10m. (a) Machine works	Cu.m	60.00				

4	Providing and spraying bituminous prime coat MC30/MC70 including cleaning the road surface using wire, brushes, broom etc. all complete before applying prime coat. (1301.1302)	Ltr.	450.00				
5	Providing and spraying bituminous tack coat MC30/MC70 including cleaning the road surface using wire, brushes, broom etc all complete before applying tack coat (1301.1302)	Ltr.	328.50				
6	Providing mixing, laying, compaction etc all complete of bitumenous premixed carpet	Cu.m	11.25				
7	Providing and laying sand seal all complete as per directed by engineer.	Sq.m	450.00				
8	Supplying and applying paint for Road marking including cleaning, watering, brooming etc. all complete (10cm. wide strip) b) More than two coats over new bitumin surface	R.M	120.00				
				Sub - Total (B)			
A				Base Cost NRs.(A+B)			
B				VAT @13% of Base Cost NRs.			
C				Grand Total Cost NRs.			

